

Sycamore Park District
Sycamore Golf Course Bridge 1 Replacement

Addendum #2

To: All Bidders
From: Jonelle Bailey, Executive Director
Date: March 10, 2022
Re: Addendum Number Two (2)
Sycamore Golf Course Bridge 1 Replacement – Sycamore Park District

Please note following questions, responses, and additional information in regard to the specifications and drawings:

Clarifications and Revisions

1. **As a reminder, the bid opening date is changed to March 29, 2022.** Sealed bids marked “Sycamore Golf Course Bridge 1 Replacement” and addressed “To Jonelle Bailey, Executive Director” shall be received on or before 10:00 am Tuesday, March 29, 2022.
2. The Fair Employment Practices Affidavit of Compliance shall be replaced with the form attached to this addendum.
3. The Substantial Completion date is changed to December 2nd, 2022. The Final Completion date is changed to December 30th, 2022.
4. Section 32 9219 Lawn Seeding: 1.2 Schedule of this section shall be replaced with the following:
 - A. Seed shall be installed between April 1 and June 15 or August 1 and December 1.The following shall be removed:
 - B. If seeding cannot be completed by November 15, Contractor shall apply a temporary erosion control seeding to stabilize the slopes throughout winter shutdown at no additional cost to the Owner.
5. Section 32 9220 Native Permanent Seeding: 1.2 Schedule of this section shall remove the following:
 - B. If seeding cannot be completed by December 1, Contractor shall apply a temporary erosion control seeding to stabilize the slopes throughout winter shutdown at no additional cost to the Owner.
6. Section 01 5700 Temporary Controls: The following sentences shall be removed from 2.3 A: “Riprap shall not be installed below the normal water level of the river per

requirements by the IDNR Floodway Construction permit.” This requirement is not applicable. Riprap shall be installed as shown on the plans.

Questions

7. Question: Is a professional land surveyor required?

Answer: Yes, construction layout and as-built survey shall be completed by an Illinois licensed professional land surveyor.

8. Question: Where is the clearing and grubbing and shrub removal?

Answer: The clearing and grubbing is on the north and south sides of the existing pedestrian bridge, on both sides of the river. The term “brush clearing” noted in four locations on Sheet 4 shall be revised to “clearing and grubbing”. The shrub to be removed is shown on Sheet 6, on the east side of the river at the compensatory storage grading area.

PLEASE NOTE ON YOUR BID PROPOSAL FORM THAT YOU HAVE RECEIVED THIS ADDENDUM OR RETURN A SIGNED COPY OF THIS MEMORANDUM WITH YOUR BID PROPOSAL FORM.

ADDENDUM #2 RECEIVED:

SIGNED: _____

DATE: _____

COMPANY: _____

FAIR EMPLOYMENT PRACTICES

AFFIDAVIT OF COMPLIANCE

NOTE: THIS AFFIDAVIT MUST BE EXECUTED AND SUBMITTED WITH THE SIGNED BID FORM. NO BIDS CAN BE ACCEPTED BY THE BOARD OF COMMISSIONERS OF THE SYCAMORE PARK DISTRICT UNLESS SAID AFFIDAVIT IS SUBMITTED CONCURRENTLY WITH THE BID.

_____, being first duly sworn, deposes and says that they are
(Name of person making the affidavit)

the _____ of _____, and that they have
(Title or Office) (Name of Contractor)

authority to make the following affidavit: that they have knowledge of the Sycamore Park District or Sycamore ordinance relating to Fair Employment Practices and know and understand the

contents thereof; that they certify hereby that _____
is an "equal opportunity employer" as defined by Section 2000 (e) of Chapter 21, Title 42 of the United States Code Annotated and Federal Executive Orders #11246 and #11375 which are incorporated herein by reference.

(Signature)

SUBSCRIBED and sworn to before me this _____ day of _____ 2022.

Notary Public